

ITB 2024-10
INTENT AND GENERAL INFORMATION
Stabilization of Private Roads
ADDENDUM NO. 5
Exhibit B
JEFFERSON COUNTY
BOARD OF COUNTY COMMISSIONERS



ADDENDUM NO. 5 TO
INVITATION TO BID NO: 2024-10
STABILIZATION OF PRIVATE ROADS
Issued January 30, 2025

SECTION 1.0 SCHEDULE OF EVENTS

Failure to comply with this or any other paragraph of this RFP shall be sufficient reason for rejection of the Proposal.

All times listed in the Schedule of Events are Eastern Standard Time (EST).

<i>Event</i>	<i>Date/Time</i>
Bid Advertisement Date	November 27, 2024
Release of Invitation to Bid	November 27, 2024
Bid Questions Due from Prospective Bidder	January 22, 2025
Responses to Bid Questions Due	January 28, 2025
BIDS DUE TO BOCC	February 7, 2025, at 3:00 PM
Posting of Intended Award	February 7, 2025
Board Consideration of Intended Award	February 20, 2025
Posting of Notice of Award	February 21, 2025

This addendum is being posted to inform prospective bidders of corrections to the basis of bid and to address the measurement of a load.

Basis of Bid

Bidder will complete the Work in accordance with the Contract Agreement for the following price(s):

Road Name - Kameron Drive	Cost
Stabilize * - 35 Loads of Limestone RB (0.2 Miles Length, 20 foot width, 6 inch depth)	
Construction - Roadway **	
Crossdrain pipe (18" x 30 ft)	
Total cost to stabilize road	

Road Name - Oakland Plantation Rd	Cost
Stabilize* - 255 Loads of Limestone RB (1.7 Miles Length, 20 foot width, 6 inch depth)	
Construction - Roadway **	
Crossdrain pipe - Qty 3 - (18" x 40 ft)	
Crossdrain pipe - Qty 3 - (24" x 40 ft)	
Total cost to stabilize road	

Road Name - Sweetfield Rd	Cost
Stabilize* - 64 Loads of Limestone RB (0.4 Miles Length, 20 foot width, 6 inch depth)	
Construction - Roadway **	
Crossdrain pipe - Qty 2 - (24" x 40 ft)	
Total cost to stabilize road	

Road Name - East/West Osprey/Murmuring Creek	Cost
Stabilize* - 225 Loads of Limestone RB (1.2 Miles Length, 18 foot width, 6 inch depth)	
Construction - Roadway **	
Crossdrain pipe - Qty 2 - (24" x 30 ft)	
Crossdrain pipe - Qty 2 - (24" x 40 ft)	
Crossdrain pipe - Murmuring Creek - Qty 2 - (24" x 40 ft)	
Total cost to stabilize road	

Road Name - CrabApple	Cost
Stabilize* - 49 Loads of Limestone RB (0.3 Miles Length, 20 foot width, 6 inch depth)	
Construction - Roadway **	
Total cost to stabilize road	

Road Name - Vista	Cost
Stabilize* - 195 Loads of Limestone RB (1.3 Miles Length, 20 foot width, 6 inch depth)	
Construction - Roadway **	
Crossdrain pipe - Qty 1 - (18" x 30 ft)	
Crossdrain pipe - Qty 1 - (24" x 30 ft)	
Total cost to stabilize road	
Road Name - Aucilla Shores Subdivision	Cost
Stabilize* - 1088 Loads of Limestone RB (11.14 Miles Length, 20 foot width, 3 inch depth)	
Construction - Roadway **	
Crossdrain pipe - Deerwood - Qty 4 - (18" x 40 ft)	
Crossdrain pipe - Deerwood - Qty 3 - (24" x 40 ft)	
Crossdrain pipe - Ashville Highland/10th - Qty 5 - (18" x 30 ft)	
Crossdrain pipe - Ashville Highland/10th - Qty 1 - (24" x 30 ft)	
Crossdrain pipe - 2nd Way - Qty 2 - (18" x 30 ft)	
Crossdrain pipe - 1st way/e. 1st Place - Qty 4 - (18" x 40 ft)	
Crossdrain pipe - 1st way/e. 1st Place - Qty 2 - (24" x 30 ft)	
Total cost to stabilize road	
GRAND TOTAL	

*** - Stabilize - The County has determined the number of loads needed for each project (A load shall be 22 tons)**

**** - Includes all items (such as mobilization, MOT, Clearing & Grubbing, Roadway installation, field engineering, some sub grade testing shall be required)**

The bid price for each item will be totaled together for a total bid price. The bidder with the lowest COMBINED TOTAL OF THE BASE BID will be considered the apparent low bidder.