



BOARD OF COUNTY COMMISSIONERS
JEFFERSON COUNTY, FLORIDA

THE KEYSTONE COUNTY-ESTABLISHED 1827
435 W WALNUT STREET; MONTICELLO, FLORIDA 32344
phone: (850)-342-0223

Jessica Gramling
District 1

Gene Hall
District 2

JT Surles
District 3

Austin Hosford
District 4

Ben White
District 5 Chair

Addendum 1
ITB 2026-13
Ashville Hwy Over Wolf Creek Bridge

Question 1:
For the Pavement Marking Question

The pay item clearly shows the White 0711-16101 and Yellow 0711-16201 pay items respectively.

0711-16101	THERMOPLASTIC STANDARD OTHER SURFACE, WHITE, SOLID, 6"	ROADWAY	GM	0.05		0.05
0711-16201	THERMOPLASTIC STANDARD OTHER SURFACES, YELLOW, SOLID, 6"	ROADWAY	GM	0.05		0.05

Question 2:

For the Plans regarding the Question there seems to be confusion due to the term "Epoxy" in the call outs related to 0413-151 Methacrylate Monomer on Sheet B1-2 & B1-3 .

Sheet B1-2

CONSTRUCTION NOTES:

ITEM 0401-70-2 RESTORE SPALLED AREAS FOR CONCRETE BRIDGES DECK PER STANDARD DECK REPAIR DETAILS. INCLUDE REPAIRS IN CONCRETE CURBS.

ITEM 0413-151 SEAL ALL TRANSVERSE AND LONGITUDINAL CRACKS IN THE DECK WITH EPOXY PER STANDARD DECK SEALING METHODS. INCLUDE CRACK SEALING IN THE CONCRETE CURBS.

ITEM 0413-154 CLEAN AND SEAL BRIDGE DECK SURFACE WITH METHACRYLATE MONOMER SEALANT.

ITEM 458-1-21 BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD TO REPLACE EXPANSION JOINT LOCATED ABOVE BENTS 2,3, AND 4.

ITEM 458-1-21 BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD TO REPLACE EXPANSION JOINT LOCATED ABOVE EACH END BENT. .

Sheet B1-3

ITEM 0413-151: SEAL ALL TRANSVERSE AND LONGITUDINAL CRACKS IN THE DECK WITH EPOXY PER STANDARD DECK SEALING METHODS. INCLUDE CRACK SEALING IN THE CONCRETE CURBS.

ITEM 0413-154 :SEAL THE BRIDGE DECK SURFACE WITH METHACRYLATE MONOMER SEALANT.

Cecil "Trey" Hightower
Clerk of Courts

Douglas Baber
County Manager

Evan Rosenthal
County Attorney



BOARD OF COUNTY COMMISSIONERS
JEFFERSON COUNTY, FLORIDA

THE KEYSTONE COUNTY-ESTABLISHED 1827
435 W WALNUT STREET; MONTICELLO, FLORIDA 32344
phone: (850)-342-0223

Jessica Gramling
District 1

Gene Hall
District 2

JT Surles
District 3

Austin Hosford
District 4

Ben White
District 5 Chair

Simply the word Epoxy should be replaced with Sealer. This would clarify the question as it related to the use of 0413-151 Methacrylate Monomer material as it is applied with 0413-154 Cleaning and Sealing Surfaces: Penetrant Sealer or Methacrylates.

0413-151	METHACRYLATE MONOMER	TOP OF DECK	GA	24		24
0413-154	CLEANING AND SEALING SURFACES: PENETRANT SEALER OR METHACRYLATES	TOP OF DECK	SF	2400		2400

Question 3:

Could you clarify the quantity for the 'Restore Spalled Areas, Latex Modified Mortarstyrene Butadiene' payitem? It currently shows a quantity of 30 CY and when this project last bid the quantity was 60 CF. It does not look like the scope changed to warrant this large change in quantity.

CY is referenced in error for pay item 0401-70-2. **Pay Item 0401-70-2 unit of measure is required to be CF (Cubic Feet). 30 CF is the correct quantity for the project.**

Cecil "Trey" Hightower
Clerk of Courts

Douglas Baber
County Manager

Evan Rosenthal
County Attorney